



SURAJ BHAN DAV PUBLIC SCHOOL

F-10/15, VASANT VIHAR, NEW DELHI-110057



Ref No: SBDAV/ 277

Date: 12/10/2020

Name of work:- REPAIRS OF EXISTING OPEN PASSAGE NEAR STAGE WITH STEPS AT SURAJ BHAN D.A.V. PUBLIC SCHOOL, VASANT VIHAR, NEW DELHI.

You are requested to send sealed quotations for execution of the above stated work. Please quote the item rates including Taxes/GST, as applicable. Copy of the tender BOQ is enclosed.

Terms & Conditions:

- 1) Work shall be carried out as per CPWD specifications. Special condition if any, they will supersede CPWD specification.
- 2) Rates quoted shall be inclusive of Taxes/GST, as applicable.
- 3) TDS will be deducted as per Income-tax Rules. .
- 4) The Security Deposit will be collected by deducting amount from the running bills of the contractors @10% of the bill amount. No interest will be paid on Security Deposit. The defect liability period being 12 months, the Security Deposit will be refunded after 12 months from completion of the work. The Earnest Money of Rs. 12,000/- by Pay Order/Bank Draft in favour of 'SURAJ BHAN DAV PUBLIC SCHOOL U/O DAVCTMS' shall be deposited at the time of submission of tender documents at reception of Suraj Bhan DAV Public School, Vasant Vihar, New Delhi on or before 19.10.2020 by 1:00 PM.
- 5) The Tender Documents will be opened on 20.10.2020 at 11:30 AM in the school.
- 6) Work completion time is one month.
- 7) Water and Electricity will be provided by the school free of cost and will not be recovered from bills of contractors.
- 8) The contractor should mention their **GST Registration Number** on the Quotation / Bills.
- 9) Work shall be carried out after putting Screen / Barricades around construction site.
- 10) In case of any accident at site / injury caused to any labour at site will be the whole responsibility of the contractor.
- 11) The contractor is required to submit at least two completion certificates of projects, completed for similar nature of jobs and cost during the past 2(Two) years.
- 12) It may be noted that client/ Architect reserves the right to accept or reject any or all the tender without assigning any reason thereof.
- 13) If any extra work is executed, it will be paid as per DSR 2018 and for Non schedule item, 15% profit will be paid.
- 14) Last date of submission of the Quotations is 19.10.2020.

Yours sincerely,


Principal

**REPAIR OF EXISTING OPEN PASSAGE NEAR STAGE WITH STEPS AT SURAJ BHAN DAV PUBLIC SCHOOL,
VASANT VIHAR, DELHI.**

SCOPE OF WORK :-

- * Dismantling the existing plaster of side Parapet walls as per Drawing.
- * Dismantling the existing Brick work for Entrance Steps of Music room as per Drawing.
- * Remove the existing kota flooring from the existing Entrance steps of Music room as per drawing.
- * Plaster of Existing side Parapet walls finish with Paint as per Drawing and specification.
- * Construction of New Ent. Steps in brick work finish with Kota stone as per Drawing and specification.
- * Leveling Existing floor for Proposed flooring as per Drawing and specification.
- * Providing & Laying Inter Locking Tiles (Paver Block) Flooring in Passage as per Drawing & Specification.
- * Providing & Fixing Existing Manhole /chamber Cover as per specification.
- * Construction Manhole /chamber with Cover as per specification.
- * Providing & Laying Proposed PVC pipe line as per specification.

Bill Of Quantity

S. No.	Item Description	Unit	Qty	Rate	Amount (Rs.)
1	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within School campus lead.	sqm	30.00		
2	Demolishing cement concrete manually/ by mechanical means including disposal of material within School campus lead as per direction of Engineer - in - charge. Nominal concrete all grade (including equivalent design mix)	Cum	1.00		
3	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within School campus lead as per direction of Engineer-in-charge. In cement mortar	Cum	2.00		
4	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within School campus lead. For thickness of tiles up to 40 mm	sqm	15.00		
5	Dismantling of old S.W. /PVS/RCC pipes including breaking of joints and bed concrete stacking of useful materials near the site within School campus lead and disposal of unserviceable materials. up to 600 mm diameter	Mtr.	15.00		
6	Dismantling of road gully chamber of various sizes including C.I. grating with frame including stacking of useful materials near the site and disposal of unserviceable materials within School campus lead including refilling the excavated gap	Each	15.00		

S. No.	Item Description	Unit	Qty	Rate	Amount (Rs.)
7	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within School campus lead.	sqm	50.00		
8	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, all loads including all lifts involved. Note:- Malba quantity is equal to dismantled material / items.	Cum	6.00		
9	Excavating trenches of required width for pipes, cables, etc including excavation for sockets, and dressing of sides, ramming of bottoms, depth up to 1.5 m including getting out the excavated soil, and then returning the soil as required, in layers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming, watering, etc. and disposing of surplus excavated soil as directed, within a lead of School campus.:				
	All kinds of soil				
	Pipes, cables etc. exceeding 20 mm dia. but not exceeding 600 mm dia.	Mtr.	18.00		
10	Supplying and filling in plinth with Jamuna sand under floors, including watering, ramming, consolidating and dressing complete.	Cum	9.00		
11	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work all level :				
	1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	Cum	2.00		
12	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure all in all shapes and sizes in :				
	Cement mortar 1:4 (1 cement : 4 coarse sand)	Cum	1.00		
13	12 mm cement plaster of mix :				
	1:4 (1 cement: 4 fine sand)	Sqm	80.00		
14	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete. Make :- JK, Birla	sqm	80.00		
15	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade Make : Asian, Berger, Nerolac				
	All work (Two coats applied @ 1.43 litre/ 10 sqm. over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm & 1mm thick wall putty).	Sqm	80.00		
16	Constructing brick masonry manhole in cement mortar 1:4 (1 cement : 4 coarse sand) with R.C.C. top slab with 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size), foundation concrete 1:4:8 mix (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size), inside plastering 12mm thick with cement mortar 1:3 (1 cement : 3 coarse sand) finished with floating coat of neat cement and making channels in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size) finished with a floating coat of neat cement complete as per standard design :				
	Inside size 90x80 cm and 45 cm deep including C.I. cover with frame (light duty) 455x610 mm internal dimensions, total weight of cover and frame to be not less than 38 kg (weight of cover 23 kg and weight of frame 15 kg) :				
	With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	Each	15.00		
17	Supplying and fixing C.I. cover with frame for manholes :				

S. No.	Item Description	Unit	Qty	Rate	Amount (Rs.)
	Rectangular C.I. cover (light duty)	Sqm	2.00		
18	Providing and laying cement concrete 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size) up to haunches of PVC pipes including bed concrete as per standard design :				
	300 mm diameter S.W. pipe	Mtr.	18.00		
19	Supplying and fixing in all position unplasticized PVC medium pipe of required dia, conforming to IS: 12818, including required hire and labour charges, fittings & accessories etc. all complete, for all depths, as per direction of Engineer-in-charge. Make - Astral / Supreme / Prince / Prakash				
	300 mm dia.	Mtr.	18.00		
20	Providing and laying factory made coloured chamfered edge Cement Concrete paver blocks of required strength, thickness & size/shape,made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of fine sand,compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with jamuna sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand in footpath, parks, lawns, drive ways or light traffic parking etc.complete as per manufacturer's specifications & direction of Engineer-in-Charge.				
	80mm thick Cement concrete paver block of M-30 grade with approved colour, design & pattern. (Rate Rs :-100 Sqft)	Sqm	225.00		
21	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) :				
	25 mm thick.	sqm	9.00		
22	Kota stone slabs 20 mm thick in risers of steps, skirting, dado and pillars laid on 12 mm (average) thick cement mortar 1:3 (1 cement 3 coarse sand) and jointed with grey cement slurry mixed with pigment to match the shade of the slabs, including rubbing and polishing complete.	sqm	15.00		
23	Extra for pre finished nosing in treads of steps of Kota stone.	Mtr.	35.00		
TOTAL					
Rebate in %					
Rebate Amount					
TOTAL (Amount after rebate)					
(These rate are including GST)					

Amount in word