

**RENOVATION OF ACTIVITY ROOM OF NURSERY BLOCK AT GROUND FLOOR AT SURAJ BHAN D.A.V PUBLIC SCHOOL AT VASANT VIHAR, DELHI**

S.NO	
1	Dismantling existing skirting tiles in existing Activity room.
2	Removing existing flush door shutter and refixing after cutting of any width in existing Activity room.
3	Providing & Fixing Vitrified floor Tiles on existing floor by camical as per specification.
4	Providing & Fixing Vitrified floor Tiles of skirting as per specification.
5	Providing & Fixing Flush door shutter with vision panel as per drawing & specification.
6	Paiting of wall & ceiling as per drawing & specification.
7	Paiting of wall & ceiling as per specification.
8	Paiting of window & MS grill as per specification.
9	New electrical work Switch & Socket at 5'-0" height at finish floor lvl. as per specification.

**BILL OF QUANTITY**

S.NO.	Item Description	Unit	Qty	Rate (Rs.)	Amount (Rs.)
1	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles up to 40 mm	sqm	10.00		
2	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	sqm	10.00		
3	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all loads including all lifts involved. Note:- Malba quantity is equal to dismantled material / items.	cum	5.00		
4	20 mm cement plaster of mix : 1:4 (1 cement: 4 coarse sand)	sqm	10.00		
5	Providing & fixing glass panes with putty and glazing clips in steel doors, windows, clerestory windows all complete. With 4.0 mm thick glass panes.	sqm	2.00		
6	Removing, fabricating & fixing existing flush door shutter including cutting, bidding size as per required & painting as per Direction Engineer - in- Charge.	LS	1.00		
7	Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade including removing old paint primer putty as per required. Two or more coats on old work.	sqm	170.00		
8	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : One or more coats on old work.	sqm	20.00		

S.NO.	Item Description	Unit	Qty	Rate (Rs.)	Amount (Rs.)
9	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption's less than 0.08% and conforming to IS : 15622 of approved make in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc., complete.				
	Size of Tile 600x600 mm	sqm	70.00		
10	Deduct for not using 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) bedding in laying of floor tiles.	sqm	70.00		
11	Fixing glazed/ Ceramic/ Vitrified floor tiles with cement based high polymer modified quick-set tile adhesive (Water based) conforming to IS: 15477, in average 3mm thickness.	sqm	70.00		
12	Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer) with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make in all colours & shade in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), including grouting the joint with white cement & matching pigments etc. complete.				
	Size of Tile 600x600 mm	sqm	5.00		
13	Wiring for light point /fan point/exhaust fan point/call bell point with 1.5 Sq.mm FRLS PVC insulated copper conductor multistrand wire in surface/recessed PVC conduit, with modular switch, modular plate, suitable size GI box and earthing the point with 1.5 sq.mm. FRLS PVC Insulated copper conductor multistand copper wire etc. as required.	Nos.	4		
14	Supplying and fixing of following sizes of medium class PVC conduit along with accessories in surface/recess including cutting the wall and making good the same in case of recessed conduit as required.				
a	20 mm	Mtr.	80		
b	25 mm	Mtr.	55		
15	Wiring for circuit/submain wiring alongwith earth wire with the following sizes of PVC insulated copper conductorwire in surface/recessed PVC conduit as required.				
a	2 x 2.5 sq.mm + 1 x 2.5 sq. mm earth wire (for ckt, 6 Amp light plug & UPS Light Plug wiring)	Mtr.	80		
b	2 x 4 sq.mm + 1 x 4 sq.mm earth wire (for power plug)	Mtr.	65		
16	Supply & Installation of the following wiring accessories, complete with recessed/surface type metal boxes, modular gridplate, faceplate and accessories in walls/partitions (Make:- Legrand)				
a	5/6 amp. Five pin socket with switch	Nos.	10		
b	15/16 amp. Five pin socket with switch	Nos.	4		
	<b>TOTAL</b>				
	Rebate in %				
	Rebate Amount				
	<b>TOTAL AMOUNT(After rebate)</b>				
	SGST @ 9%				
	CGST @ 9%				
	<b>GRAND TOTAL (Including GST)</b>				