

SURAJ BHAN D.A.V.PUBLIC SCHOOL
F-10/15, Vasant Vihar, New Delhi - 110 057 Ph. : 26149082 / 26149371
Website : www.sbdav.com

Notice for Inviting Tenders

Sealed tenders are invited from qualified and reputed Contractors for construction of Basket Ball Court in the school, approximate cost Rs.18 Lakhs.

Tender documents can be collected from School Reception or can be downloaded from School's Website www.sbdav.com . Tender fee Rs. 500/-

Last date for submission of sealed Tender is 16th October, 2023 till 2:00 p.m.

The School management has the right to accept or reject the Tender without assigning any reason.


PRINCIPAL



SURAJ BHAN DAV PUBLIC SCHOOL

F-10/15, VASANT VIHAR, NEW DELHI-110057



INTERNATIONAL
SCHOOL AWARD
2017-2020

Dt: 07/10/2023


To,

Name of work:- CONSTRUCTION OF BASKET BALL COURT AT S. B. D.A.V.PUBLIC SCHOOL, VASANT VIHAR, NEW DELHI.

You are requested to send sealed quotations for execution of above stated work. Quote the item rates are including GST. Copy of tender BOQ is enclosed.

Terms & conditions

- 1) Work shall be carried out as per CPWD specifications. Special condition if any, they will supersede CPWD specification.
- 2) Rates quoted shall be including of GST.
- 3) All deduction i.e. **TDS & Labour Cess** shall be as per norms.
- 4) The security deposit will be collected by deductions from the running bills of the contractors @10% of the value of work done. No interest shall be paid on Security deposit. Refunded of security after completion the work, the defect liability period is 12 month. The **Earnest Money of Rs. 35,000/-** by pay order/Bank draft in favour of **SURAJ BHAN DAV PUBLIC SCHOOL U/o DAVCTMS** deposited at the time of submission of tender in the office of SURAJ BHAN DAV Public School, Vasant Vihar, New Delhi on 16.10.2023, before 2:00 PM.
- 5) The Tender Document will be opened on 17.10.2023 at 11:30 a.m. .
- 6) Work completion time is One month.
- 7) **Water & Electricity** will be Provided by the school free of cost.
- 8) The contractor should mention their **GST registration number** on quotation& on bill.
- 9) Work should be carried out after putting screen / Barricades around construction site.


Dr. ANITA AHUJA

Principal
SURAJ BHAN DAV PUBLIC SCHOOL
F-10/15, VASANT VIHAR,
NEW DELHI-110057

MANAGED BY - DAV COLLEGE MANAGING COMMITTEE, CHITRA GUPTA ROAD, NEW DELHI-110 055

Tel: +91-11-26149082, 26149371 Email: sb_dav@yahoo.co.in, sbdav_admn@yahoo.in Website: www.sbdav.com



SURAJ BHAN DAV PUBLIC SCHOOL

F-10/15, VASANT VIHAR, NEW DELHI-110057



INTERNATIONAL
SCHOOL AWARD
2017-2020

- 10) For HPU cushion sports flooring the vendor should provide 5 Years Guarantee period on affidavit/ stamp paper of Rs. 100/-.
- 11) In case of any accident / injury caused to the labour at site is fully responsibility of contractor.
- 12) No Price Escalation will be given during the Construction period.
- 13) Noise producing work will be done after school time or with the permission of the School authorities.
- 14) No advance payment and no advance against material will be given.
- 15) Quoted rates are valid for 3 months.
- 16) All Local bodies like MCD, Police etc. will be managed by the vendor at their own cost. No payment will be given to vendor against this.
- 17) If due to any reason the work stopped during the time of construction, no extra payment /extra rate will be paid for delay by the school.
- 18) During work proper water sprinkling done at site so that no air pollution will be occurred.
- 19) Vendor has to Submit the **Labour Insurance Certificate** to school before start of work.
- 20) You are requested to submit at least two completion certificates of projects, completed for similar nature of jobs and cost during past 2(Two) years.
- 21) It may be noted that client/ Architect reserve the right to accept or reject any or all the tender without assigning any reason thereof.
- 22) If any extra work executed it will be paid as per DSR 2021 and for Non schedule item, 10% profit will be paid.
- 23) Last date of submission of tender is 16.10.2023.

Yours sincerely,

Principal
S.B.D.A.V .Public School
Vasant Vihar

Enclose : -BOQ

Name of Work:- Construction of Basket Ball Court at S.B..D.A.V. Public School, Vasant Vihar, Delhi.

Bill of Quantity

DATE:- -09-2023

S No.	Descriptions of Items	Unit	Quantity	Rate	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30cm in depth. 1.5m in width as well as 10 sqm on plan) including the cost of disposal of excavated earth, lead up within school site as directed by EIC. and lift up to 1.5m, disposed earth to be levelled and neatly dressed.				
	All kinds of soil	cum	221.76		
2	Preparation and consolidation of sub grade with power road roller of 8 to 12 tonne capacity after excavating earth to an average of 22.5 cm. depth, dressing to camber and consolidating with road roller including making good the undulations etc. and re-rolling the sub grade and including the cost of disposal of surplus earth with school campus as directed by EIC	sqm	610		
3	Supplying and stacking at site as directed by EIC.				
	90 mm to 45 mm size stone aggregate.	cum	90		
4	Laying, spreading and compacting stone aggregate of specified sizes to WBM specifications in uniform thickness, hand picking, rolling with 3 wheeled road / vibratory roller 8-10 tonne capacity in stages to proper grade and camber, applying and brooming requisite type of screening / binding material to fill up interstices of coarse aggregate, watering and compacting to the required density as directed by EIC..	cum	90		
5	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work up to plinth level :				
	1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size). (Cement make - Ultratech, Ambuja, ACC)	cum	73.92		
6	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : (Paint Make : Nerolac, Asian paints, Berger, Deluxe)				
	Two or more coats on new work.	sqm	20		

S.No.	Descriptions of Items	Unit	Quantity	Rate	Amount
7	Providing and fixing Basket ball pole (including the cost of Foundation work) of 2.2 mtrs high finished with approved enamel paint madeup of Heavy iron 8" dia of 5 mm thk. & middle support of 80mm dia of 4mm thk. extension as per basketball federation of India including the cost of R.C.C. Foundation & all work necessary to fix the pole at site. . The acrylic basket ball back board made without ant water mark/scratch, water proof/ weather proof of size 1.80X1.08 M, 20mm thick, along with steel perimeter frame of 35mm x 4mm with computerized lining of paint and tapered/ chrome plated Nut bolts are used to fix the angle iron support with basket ball ring and basket ball net of approved brand like WELCO , Keepfit etc. including clips, nuts boltsand screw etc.complete as per direction of Engineer-in- charge.	each	2		
8	Supply and apply of HPU cushion sports flooring having one coat of PU primer , one Coat of Synthetic Resurfacer, three layers of Moldo Rubber Cushion, One layer of Pre – Coating, TWO coat of water based HPU Top Coat, One Coat of HPU line marking as per requirement after cleaning of surface & roughing the exsiting kota flooring and removing all dust and lose particles from the surface. Note:- -Including the cost of preparation of surafce for before treatment/Painting. & Cleaning the site before handed over. -The vendor should provide 5 Years Guranttee period. -Including stay & food of Labours. (HPU Make : Moldo Sports, Flying Fox sports, Pro Plastic.)	sqm	610		
	TOTAL =				
	Rebate in %				
	Rebate in Amount				
	NET TOTAL =				
	(These rate are including GST)				

Name of Work:- Construction of Basket Ball Court at S.B..D.A.V. Public School, Vasant Vihar, Delhi.

Measurement Sheet

S.NO.		UNIT	NO	L	W	D/H	Quantity
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30cm in depth, 1.5m in width as well as 10 sqm on plan) including disposal of excavated earth, lead up to 50m and lift up to 1.5m, disposed earth to be levelled and neatly dressed.						
	All kinds of soil	cum	1	21	32	0.3	201.6
							20.16
	TOTAL =						221.76
2	Preparation and consolidation of sub grade with power road roller of 8 to 12 tonne capacity after excavating earth to an average of 22.5 cm. depth, dressing to camber and consolidating with road roller including making good the undulations etc. and re-rolling the sub grade and disposal of surplus earth with lead up to 50 metres.						
		sqm	1	21	32		672
							67.2
	TOTAL =						739.2
3	Supplying and stacking at site						
	90 mm to 45 mm size stone aggregate.	cum	1	21	32	0.2	134.4
							13.44
	TOTAL =						147.84
4	Laying, spreading and compacting stone aggregate of specified sizes to WBM specifications in uniform thickness, hand picking, rolling with 3 wheeled road / vibratory roller 8-10 tonne capacity in stages to proper grade and camber, applying and brooming requisite type of screening / binding material to fill up interstices of coarse aggregate, watering and compacting to the required density.						
		cum					147.84
5	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work up to plinth level :						
	1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size).	cum					
			1	21	32	0.1	67.2
							6.72
	TOTAL =						73.92
6	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :						
	Two or more coats on new work.	sqm					20
7	Providing and fixing acrylic basket ball back board of size 1.80X1.08 M, 20mm thick, along with steel perimeter frame, basket ball ring and basket ball net of approved brand like WELCO etc. including clips, nuts bolts and screw etc. complete as per direction of Engineer-in-charge.						
		each					2
8	Supply and apply of HPU cushion sports flooring having one coat of PU primer, one Coat of Synthetic Resurfacer, three layers of Moldo Rubber Cushion, One layer of Pre – Coating, TWO coat of water based HPU Top Coat, One Coat of HPU line marking. after cleaning of surface & roughing the existing kota flooring and removing all dust and loose particles from the surface.						
		sqm	1	21	32		672
							67.2
	Total =						739.2